

ЗАТВЕРДЖЕНО

**ДЕФЕКТНИЙ АКТ**

на капітальний ремонт Поточний ремонт приміщень Нивотрудівського ліцею Нивотрудівської сільської ради, за адресою: с.НиваТрудова, вул. Південна 7


Умови виконання робіт

Об'єми робіт

№ Ч.ч.	Найменування робіт і витрат	Одиниця виміру	Кількість	Примітка
1	2	3	4	5
	Демонтажні роботи			
1	(Демонтаж) Улаштування цементної стяжки товщиною 20 мм по бетонній основі площею до 20 м2	м2	54,93	
2	Розбирання покриттів підлог з лінолеуму та реліну	м2	54,93	
3	Розбирання дерев'яних плінтусів	м	30,28	
4	Демонтаж радіаторів масою до 80 кг	шт	4	
5	Знімання підвіконних дощок в кам'яних будівлях	м2	1,332	
6	Демонтаж дверних коробок	шт	1	
7	Знімання дверних полотен	м2	1,9008	
8	(Демонтаж) Прокладання трубопроводів водопостачання з труб поліетиленових [поліпропіленових] напірних діаметром 25 мм	м	36	
9	Демонтаж вимикачів, розеток	шт	9	
10	Демонтаж світильників	шт	18	
11	Знімання шпалер простих та поліпшених	м2	79,07	
12	Очищення приміщень від сміття	т	7,6	
13	Навантаження сміття вручну	т	0,47	
14	Перевезення сміття до 30 км	т	0,47	
	Стіни			
15	Улаштування обшивки стін гіпсокартонними плитами [фальшстіни] по металевому каркасу	м2	79,07	
16	Шпаклювання стін мінеральною шпаклівкою	м2	79,07	
17	Високоякісне фарбування полівінілацетатними водоемульсійними сумішами стін по збірних конструкціях, підготовлених під фарбування (фігурна)	м2	79,07	
	Стеля			
18	Улаштування каркасу підвісних стель	м2	54,93	
19	Укладання плит стельових в каркас стелі	м2	51,69	
	Підлога			
20	Улаштування стяжок бетонних товщиною 20 мм	м2	54,93	
21	Додавати або виключати на кожні 5 мм зміни товщини бетонних стяжок до 80мм	м2	54,93	
22	Улаштування покриття з лінолеуму площею покриття понад 10 м2	м2	54,93	
23	Улаштування плінтусів полівінілхлоридних на шурупах	м	30,28	

1	2	3	4	5
24	Улаштування порожків на шурупах	м	1	
25	Улаштування гумового пандусу	м	2,44	
	прорізи			
26	Розширення дверних прорізів з посиленням	шт	1	
27	Установлення дверних полотен внутрішніх міжкімнатних	шт	1	
28	Установлення пластикових підвіконних дошок	м	4,44	
	Укоси			
29	Ґрунтування бетонних і обштукатурених поверхонь	м2	2,73	
30	Улаштування обшивки укосів гіпсокартонними і гіпсоволокнистими листами з кріпленням на клеї	м2	2,73	
31	Улаштування обшивки укосів гіпсокартонними і гіпсоволокнистими листами з кріпленням шурупами з улаштуванням металевого каркасу без утеплення	м2	7,13	
32	Шпаклювання укосів мінеральною шпаклівкою	м2	9,86	
33	Додавати на 1 мм зміни товщини шпаклівки	м2	9,86	
34	Високоякісне фарбування полівінілацетатними водоемульсійними сумішами укосів	м2	9,86	
	Електромонтажні роботи			
35	Прокладання кабелю у гофрі, на скобах	м	15	
36	Затягування проводу в труби	м	15	
37	Прокладання проводів при схованій проводці в гофротрубі	м	100	
38	Установлення штепсельних розеток	шт	8	
39	Установлення вимикачів утопленого типу при схованій проводці, 2-клавішних	шт	1	
40	Монтаж світильників	шт	9	
41	Установлення щитків освітлювальних групових масою до 3 кг у готовій ніші або на стіні	шт	1	
42	Установлення автоматичних вимикачів пакетних на струм до 25 А	шт	2	
	Опалення			
43	Прокладання трубопроводів опалення з труб поліетиленових [поліпропіленових] напірних діаметром 25 мм	м	36	
44	Установлення опалювальних радіаторів біметалевих	шт	4	
	Пандус			
45	Розбирання покриттів підлог з керамічних плиток	м2	0,72	
46	Улаштування покриттів східців і підсхідців з керамічних плиток розміром 30х30 см на розчині із сухої клеючої суміші	м2	0,72	
47	Монтаж металоконструкцій сходів, площадок, огорожень	т	0,8	
48	Ґрунтування металевих поверхонь за один раз ґрунтовкою ГФ-021	м2	19	
49	Фарбування цратчастих конструкцій	м2	19	

Склав





DEFECTIVE ACT

for major repairs Current renovation of the premises of the Nivotrudov Lyceum of the Nivotrudov Village Council, at the address: village of NivaTrudova, 7 Pivdenna St.

Conditions for performing work

Scope of work

No. Part No.	Name of work and costs	Unit of measurement	Number	Note
1	2	3	4	5
	Dismantling work			
1	(Dismantling) Installation of a 20 mm thick cement screed on a concrete base with an area of up to 20 m2	m2	54,93	
2	Dismantling linoleum and relin flooring	m2	54,93	
3	Dismantling wooden baseboards	m	30,28	
4	Dismantling of radiators weighing up to 80 kg	pcs	4	
5	Removing window sills in stone buildings	m2	1,332	
6	Dismantling door frames	pcs	1	
7	Removing door panels	m2	1,9008	
8	(Dismantling) Laying water supply pipelines from polyethylene [polypropylene] pressure pipes with a diameter of 25 mm	m	36	
9	Dismantling of switches and sockets	pcs	9	
10	Dismantling of lamps	pcs	18	
11	Simple and advanced wallpaper removal	m2	79,07	
12	Cleaning premises from garbage	t	7,6	
13	Manual garbage loading	t	0,47	
14	Garbage transportation up to 30 km	t	0,47	
	Walls			
15	Installation of wall cladding with plasterboard panels [false walls] on a metal frame	m2	79,07	
16	Puttying walls with mineral putty	m2	79,07	
17	High-quality painting with polyvinyl acetate water-based emulsion mixtures of walls on prefabricated structures prepared for painting (curved)	m2	79,07	
	Ceiling			
18	Installation of the frame of suspended ceilings	m2	54,93	
19	Laying ceiling tiles in the ceiling frame	m2	51,69	
	Floor			
20	Arrangement of concrete screeds 20 mm thick	m2	54,93	
21	Add or exclude for every 5 mm change in the thickness of concrete screeds up to 80 mm	m2	54,93	
22	Installation of linoleum covering with a covering area of more than 10 m2	m2	54,93	
23	Installation of polyvinyl chloride skirting boards with screws	m	30,28	

1	2	3	4	5
24	Installing thresholds on screws	m	1	
25	Rubber ramp installation slots	m	2,44	
26	Widening doorways with reinforcement	pcs	1	
27	Installation of interior door panels	pcs	1	
28	Installation of plastic window sills Slopes	m	4,44	
29	Priming concrete and plastered surfaces	m2	2,73	
30	Arrangement of slopes sheathing with plasterboard and gypsum fiber sheets with adhesive fastening	m2	2,73	
31	Installation of slope cladding with plasterboard and gypsum fiber sheets with screw fastening and installation of a metal frame without insulation	m2	7,13	
32	Putting slopes with mineral putty	m2	9,86	
33	Add 1 mm of putty thickness changes	m2	9,86	
34	High-quality painting of slopes with polyvinyl acetate water-based emulsion mixtures	m2	9,86	
	Electrical installation work			
35	Cable laying in corrugation, on brackets	m	15	
36	Tightening the wire into the pipes	m	15	
37	Laying wires with hidden wiring in corrugated pipe	m	100	
38	Installing power outlets	pcs	8	
39	Installation of recessed switches with concealed wiring, 2-button	pcs	1	
40	Installation of lamps	pcs	9	
41	Installation of group lighting panels weighing up to 3 kg in a finished niche or on the wall	pcs	1	
42	Installation of package circuit breakers for current up to 25 A	pcs	2	
	Heating			
43	Laying heating pipelines from polyethylene [polypropylene] pressure pipes with a diameter of 25 mm	m	36	
44	Installation of bimetallic heating radiators	pcs	4	
	Ramp			
45	Dismantling ceramic tile floors	m2	0,72	
46	Arrangement of coverings of steps and risers made of ceramic tiles measuring 30x30 cm on a solution of dry adhesive mixture	m2	0,72	
47	Installation of metal structures of stairs, platforms, fences	t	0,8	
48	Priming metal surfaces in one go with primer GF-021	m2	19	
49	Painting lattice structures	m2	19	

Compiled by _____
 [position, signature (initials, last name)]

